

# GROUP 4 MECHATRONICS SYSTEM(up to #1000)


## 1. ALL ACTUATORS SPEED ARE SLOW(up to #0179)

Boom, Arm, Bucket, Swing and travel speed are slow, but engine speed is good.

Spec : H-mode 2250 ± 50rpm                      S-mode 2150 ± 50rpm

Before carrying out below procedure, check all the related connectors are properly inserted.


### 1) INSPECTION PROCEDURE



### Wiring diagram

Normal : —————

Emergency : - - - - -



21076MS01


## 1-1. ALL ACTUATORS SPEED ARE SLOW(from #0180 to #1000)

Boom, Arm, Bucket, Swing and travel speed are slow, but engine speed is good.


Spec : H-mode 2250 ± 50rpm      S-mode 2150 ± 50rpm

Before carrying out below procedure, check all the related connectors are properly inserted.

### 1) INSPECTION PROCEDURE



### Wiring diagram



21076MS51


## 2) TEST PROCEDURE

- (1) **Test 1** : Check resistance at connector CN-50(8)-(36).

Starting key OFF.

Disconnect connector CN-50.

Check resistance between pin and at connector CN-50(8)-(36).




- (2) **Test 2** : Check resistance at connector CN-75.

Starting key OFF.

Disconnect connector CN-75 from EPPR valve at main hydraulic pump.

Check resistance between 2 lines as figure.



- (3) **Test 3** : Check electric current at EPPR valve.


Install multimeter as figure.

Start engine.

Set the accel dial at "10"(MAX)

Set S-mode and cancel auto decel mode.

If tachometer show approx  $2150 \pm 50$ rpm, check electric current.



(2) **Test 4** : Check pressure at EPPR valve.  
Remove plug and connect pressure gauge as figure.

- Gauge capacity : 0 to 40~50kgf/cm<sup>2</sup>  
(0 to 570~710psi)

Start engine.

Set the accel dial at "10"(Max)


Set S-mode and cancel auto decel mode.

If tachometer show approx 2150 ± 50rpm,  
check pressure.

If pressure is not correct, adjust it.

After adjust, test the machine.

SPEC : 5~20kgf/cm<sup>2</sup>(70~280psi)



(210-7) 6-39(1)




## 2) TEST PROCEDURE

- (1) **Test 5** : Check resistance between CN-50 (12)-(23).

Starting key OFF.

Disconnect connector CN-50 from CPU controller.

Check resistance as figure.



- (2) **Test 6** : Check tachometer(Work properly or not)

Start engine.

Check tachometer reading.

Unit : rpm


Spec			Remark
Tier-I (~#1000)	H	2250 ± 50	Check rpm after cancel the Auto decel mode.
	S	2150 ± 50	
Tier-II (#1001~)	H	2150 ± 50	Check rpm after cancel the Auto decel mode.
	S	2050 ± 50	

(3) **Test 7** : Check resistance between CN-51 (25) and CN-51(26).

Starting key OFF.

Disconnect connector CN-51 from CPU controller.

Check resistance as figure.




(4) **Test 8** : Check resistance at speed sensor.

Starting key OFF.

Disconnect connector CD-17 of speed sensor at engine flywheel housing.


Check resistance as figure.




### 3. ENGINE STALL(up to #0179)

Before carrying out below procedure, check all the related connectors are properly inserted.

#### 1) INSPECTION PROCEDURE



#### Wiring diagram




29076MS01




### 3-1. ENGINE STALL(from #0180 to #1000)

Before carrying out below procedure, check all the related connectors are properly inserted.

#### 1) INSPECTION PROCEDURE




#### Wiring diagram




21076MS51

## 2) TEST PROCEDURE

- (1) **Test 9** : Check electric current at EPPR valve at S-mode  
Install multimeter as figure.  
Start engine.  
Set the accel dial at "10"(max)  
Set S-mode with  $2150 \pm 50$ rpm.  
Check electric current.




- (2) **Test 10** : Check pressure at EPPR valve at S-mode  
Connect pressure gauge at EPPR valve.  
Start engine.  
Set the accel dial at "10"(max)  
Set S-mode with  $2150 \pm 50$ rpm.  
Operate bucket lever completely push or pull.  
Hold arm lever at the end of stroke.  
Check pressure at relief position.




#### 4. MALFUNCTION OF CLUSTER OR MODE SELECTION SYSTEM

Before carrying out below procedure, check all the related connectors are properly inserted.

##### 1) INSPECTION PROCEDURE




##### Wiring diagram




## 5. SLOW ACTION OF ENGINE SPEED CHANGE WHEN CHANGE THE MODE

Before carrying out below procedure, check all the related connectors are properly inserted.

### 1) INSPECTION PROCEDURE



### Wiring diagram




29076MS03

## 2) TEST PROCEDURE


- (1) **Test 11** : Check resistance.  
Starting key OFF.  
Disconnect connector CN-50 from CPU controller.  
Check resistance between CN-50(12)-(23) as figure.

SPEC : 1~2




29076MS04

- (2) **Test 12** : Check voltage and resistance.  
 Check resistance between CN-51(20)-  
 (22).
- Starting key OFF.
  - Disconnect connector CN-51 from CPU controller.
  - Check resistance value with multimeter as figure.



Check voltage between CN-51(20) and  
 CN-51(21).

- Prepare 2 pieces of thin sharp pin, steel or copper.
- Starting key ON.
- Insert prepared pins to rear side of connectors : One pin to CN-51(20)  
 Other pin to CN-51(21)
- Check voltage.




## 6. AUTO DECEL SYSTEM DOES NOT WORK

Before carrying out below procedure, check all the related connectors are properly inserted.

### 1) INSPECTION PROCEDURE

		Cause	Remedy
<div style="border: 1px solid black; padding: 5px; width: fit-content;">                     Check resistance between CN-51 (1)-GND and CN-51(13)-GND                 </div> <p>SPEC :                      Actuator operating : 4~5V                      Actuator stop : 0~1V                      See TEST 13                      See TEST 14</p>	YES	Defective CPU controller	Replace
	NO	Short circuit or poor connection between CN-51(1), (13)- pressure switches	Replace or repair
	NO	Defective auto decel pressure switch	Replace

### Wiring diagram



29076MS10

## 2) TEST PROCEDURE

- (1) **Test 13** : Check voltage at CN-51(1) and ground.

Prepare 1 piece of thin sharp pin, steel or copper.

Starting key ON.

Insert prepared pin to rear side of connectors : One pin to (1) of CN-51.

Check voltage as figure.

- (2) **Test 14** : Check voltage at CN-51(13) and ground.


Prepare 1 piece of thin sharp pin, steel or copper

Starting key ON.

Insert prepared pin to rear side of connectors : One pin to (13) of CN-51.

Check voltage as figure.

SPEC : Actuator stop : 4~5V  
Actuator operating : 0~1V




29076MS11




## 7. MALFUNCTION OF WARMING UP

Before carrying out below procedure, check all the related connectors are properly inserted.

### 1) INSPECTION PROCEDURE



### Wiring diagram




21076ES53


## 8. MALFUNCTION OF POWER MAX

Before carrying out below procedure, check all the related connectors are properly inserted.

### 1) INSPECTION PROCEDURE



### Wiring diagram



29076MS13


## 2) TEST PROCEDURE

- (1) **Test 15:** Check voltage between connector CN-88 - GND.

Start key ON.

Disconnect connector CN-88 from power max solenoid valve.

Check voltage as figure.




- (2) **Test 16:** Check resistance between connector CN-51(2)-GND.

Starting key OFF.

Remove CPU controller and disconnect connector CN-51 from CPU controller.

Check resistance as figure.



## GROUP 5 MECHATRONICS SYSTEM (#1001 and up, TIER II)


### 1. ALL ACTUATORS SPEED ARE SLOW

Boom, Arm, Bucket, Swing and travel speed are slow, but engine speed is good.


Spec : H-mode 2150 ± 50rpm                      S-mode 2050 ± 50rpm

Before carrying out below procedure, check all the related connectors are properly inserted.

#### 1) INSPECTION PROCEDURE



#### Wiring diagram




- (1) **Test 2** : Check resistance at connector CN-75.

Starting key OFF.

Disconnect connector CN-75 from EPPR valve at main hydraulic pump.

Check resistance between 2 lines as figure.



- (2) **Test 3** : Check electric current at EPPR valve.


Install multimeter as figure.

Start engine.

Set the accel dial at "10"(MAX)

Set S-mode and cancel auto decel mode.

If tachometer show approx  $2050 \pm 50$ rpm check electric current.



- (3) **Test 4** : Check pressure at EPPR valve.

Remove plug and connect pressure gauge as figure.

- Gauge capacity : 0 to 40~50kgf/cm<sup>2</sup>  
(0 to 570~710psi)

Start engine.


Set the accel dial at "10"(Max).

Set S-mode and cancel auto decel mode.

If tachometer show approx  $2050 \pm 50$ rpm check pressure.

If pressure is not correct, adjust it.


After adjust, test the machine.




## 2. ENGINE STALL

Before carrying out below procedure, check all the related connectors are properly inserted.

### 1) INSPECTION PROCEDURE



### Wiring diagram



21076MS51

## 2) TEST PROCEDURE

### (1) Test 3 : Check electric current at EPPR valve at S-mode


Install multimeter as figure.

Start engine.

Set the accel dial at "10"(max)

Set S-mode with  $2050 \pm 50$ rpm.

Check electric current.



### (2) Test 4 : Check pressure at EPPR valve at S-mode

Connect pressure gauge at EPPR valve.

Start engine.

Set the accel dial at "10"(max)

Set S-mode with  $2050 \pm 50$ rpm.

Operate bucket lever completely push or pull.

Hold arm lever at the end of stroke.

Check pressure at relief position.

